



N02

FRONT VIEW




INNER SPACE VIEW

FRONT VIEW



SECTION



SECTION

RECEPTION DESK - INFO SPOT

N02

DESCRIPTION

RECEPTION DESK

Information desk, total size 340x65x115cm. The desk is of skew “P” shape, made of veneered medium-density fiberboard (MDF) d=25mm, ash tree veneer or equivalent. Frontal cord concealer is made of MDF d=25mm, colour white RAL 9003 - high gloss.

Inner side of the desk - desktop is made of MDF, white colour RAL 9003, high gloss, thickness d=25mm. Lateral parts, cable mask and drawer fronts are made of MDF, thickness d=19mm. drawers are made of white smooth refined chipboard d=18mm, with abs tape of the same colour and pattern.

Drawers are equipped with telescopic slides l=300mm, with slow-motion mechanism, and matte aluminum handles. Fittings - Hafele type or equivalent.

A Ø60mm opening is foreseen at the bottom surface for cables together with matte aluminum downlight.

GENERAL NOTE:

MDF - Medium density fibreboard
MVC - Melamine faced chipboard
HDF - High-density fiberboard

element	name	dimensions axbxc	number
N02	RECEPTION DESK / INFO SPOT	340x65x115	1

 projekovanje, konsalting, inženjering Beograd, Kneza Miloša 82 tel. 011 361 4634, 2656 251 www.domaa.rs e-mail: offices@domaa.rs	investor EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
	building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade	
 društvo za projektovanje, konsalting i inženjering Dubrovačka 14, Beograd; tel:011/2463-344; e-mail: info@aerprojekt.com	type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXHISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE	
	drawing	NEWLY DESIGNED - FURNITURE GROUND FLOOR	
part of design	scale	date	drawing No
ARCHITECTURAL	1:20	october 2014	AF_04