


1	existing brick wall	~68.0cm
2	waterproof - penetrate and polymercement lay.	0.5cm
3	mineral wool 100kg	5.0cm
4	PE foil	
5	gypsum board on subconstruction	2x1.25cm
6	interior finishing	



1	existing brick wall	25.0cm
2	waterproof - penetrate and polymercement lay.	0.5cm
3	mineral wool 100kg	5.0cm
4	PE foil	
5	airspace (gypsum subconstruction)	10.0cm
6	gypsum board on subconstruction	2x1.25cm
7	interior finishing	